TUMKUR DIVISION.

ADVERTISEMENT.

The 22nd October 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 22nd November 1891, for restoring Kyatagenkere Tank of Pavagada Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st March 1895.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Items of Work.	Per.	Quantity.	Rate.	Cost.
				Rs.
Bund—				
Earthwork	C. Yd.	108,813		
Earthwork excavation	Do	4,916		
New stone work	Do	4,799		
Old stone work	Do	3,000		
Grade stones	Each	35		
B. M. stones	Do	2		
Removing sand and boiling water	..	..	Lump sum	1,000
Sluice—				
Lump sum	..	..	.. .. ..	2,000
WASTE WEIRS.				
Left Waste Weir—				
Rock chiselling	S. Ft.	2,410		
Burnt stone in chunam	C. Ft.	12,262		
Brick in chunam	Do	9,033		
Chunam plastering	Sq.	45·23		
Chunam pointing	Do	30·00		
Covering slabs	S. Ft.	713		
New stone work	C. Yd.	100		
Right Waste Weir—				
Excavation	C. Yd.	825		
Brick in chunam	C. Ft.	5,029		
Chunam plastering	Sq.	15·70		
Covering slabs	S. Ft.	403		
New stone work	C. Yd.	721		
Distribution—				
Irrigation channel..	..	..	Lump sum	1,000
Masonry aqueduct	..	..	Lump sum	1,000
Miscellaneous—				
Compensation for lands submerged	..	..	Lump sum	600

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kyatagenkere Tank of Pavagada Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the